

**SECTION 03400**  
**CLEARING FOR CONSTRUCTION ACCESS**

**PART 1 - GENERAL**

**1.01 WORK INCLUDED**

- A. Excavation, grading, cutting and removal of trees, shrubs and underbrush, and the removal of any debris existing above natural ground surface and within the cleared area necessary to permit the construction of the improvements.

**1.02 RELATED WORK**

- A.. Section 02605 - Manholes
- B. Section 02730 - Sanitary Sewer Pipelines
- C. Section 02732 - Sanitary Sewer Service Lines
- D. Section 02734 - Inspection and Testing of Sanitary Sewer Pipelines, Manholes and Service Lines

**1.03 PROTECTION**

- A. In all cases the Contractor is responsible for protecting public and private property and protecting any person or persons who might be injured as a result of the Contractor's work.
- B. The Contractor is responsible for verifying locations of all utilities and contacting the Arkansas One Call System before excavating.

## **PART 2 - MATERIALS**

Not used

## **PART 3 - EXECUTION**

### **3.01 GENERAL**

- A. The Contractor will be required to submit a plan to build access roads/trails for approval by the Engineer of Record.
- B. Trees, shrubs, underbrush and debris removed from the improvement right of way shall be disposed of by the Contractor in a manner approved by the Engineer of Record.

**END OF SECTION 03400**